

CONSTRUCTION CONTRACTOR PERSONNEL GUIDELINES AND WORK RULES

Mayo Clinic Health System – Southwest Minnesota

Emergencies

Report any emergency (medical / fire / security / chemical spill) to Security and/or Facilities immediately. Local contact information to be provided for the specific location you are working at.

General Information

All job direction, questions and interaction with Owner will be through the designated Owner Representative(s).

- Ensuring patient safety, security, confidentiality and comfort is basic to all Owner activities. Contractor personnel are asked to perform work always considering the needs of the patients first.
- Normal working hours are 7:00 a.m. – 3:30 p.m. Contractor lunch period is 12:00 a.m. – 12:30 noon in Owner designated areas. Any deviation from these hours requires prior approval. Breaks will be taken at the job site or other break areas as designated by the Owner.
- Restrooms for use by Contractor personnel will be identified by the Owner.
- All construction related personnel and material access and egress to grounds and buildings will be coordinated with the Owner.
- Smoking (including e-cigs), chewing tobacco, firearms/weapons, violence, harassment, alcoholic beverages, illicit drugs, horseplay, and swearing are strictly prohibited on the Owner's property.
- All Contractor personnel must dress in clean and presentable clothing.
- All Contractors are to receive and wear an Owner access/identification card in order to work on the Owner's property. Access cards must be returned upon Contractor's completion of their work relationship.

Owner shall have the absolute right in its sole discretion to prohibit Contractor personnel from continuing to perform work if Contractor personnel have (1) acted inappropriately; (2) interfered with any of Owner's employees/contractors/ agents; or (3) violated any of Owner's policies and procedures.

External Requirements

The Federal Occupational Safety and Health Administration requires that Contractor personnel receive basic training from their employer about hazardous substances, harmful physical agents and infectious agents associated with their professions before performing any work. Examples of hazards include noise, heat, asbestos, chemicals (such as solvents), and infectious agents (their general description and transportation). The Owner provides additional information necessary to work in the Owner's following areas:

- Radiology rooms
- Nuclear medicine rooms
- Magnetic resonance imaging (MRI) rooms
- Fume hoods and their roof top exhausts
- Patient isolation rooms
- Laser rooms
- Heliport
- Sterile processing spaces / clean rooms
- Power Plants
- Data center
- Surgical services area
- Radiation oncology/Gamma knife
- Laboratories/laboratory buildings
- Waste handling
- Autopsy
- Animal care facilities
- Psychiatry or restricted patient units
- Signed "warning" or "restricted" space

Contractor personnel working in these areas should contact their Owner Representative(s) who will arrange for site-specific training prior to commencing work on a project. The Owner will supply protective clothing and equipment if necessary.

Job Site Housekeeping and Material Staging

Contractor personnel will clean the work site thoroughly each day after job completion. Once an area is given a final cleaning, construction personnel will not be allowed to return to the area unless given specific authorization from the Owner. Ceiling tiles will be reinstalled as soon as possible after removal. All smoke and fire walls and shafts and floor openings where work is performed outside of the enclosed construction project area will be patched within the same work shift to maintain their fire related integrity. Contractor deliveries may be received on Owner's loading dock (if exists), but Owner support, including equipment, is not provided. Dock activity demands that its use must be closely coordinated with the Owner. All material staging areas must be approved by the Owner.

Noise

Construction noise transmits easily throughout patient and staff areas. Use caution when making loud noises. Before starting noisy work, especially hammer drills, coordinate with the Owner to avoid disturbances of adjacent areas. Music generating devices, two-way radios, and cellular phones are not to be used in patient care areas.

Safety

- Contractor accepts complete responsibility for the health and safety of its employees (its subcontractors' employees); the protection of the Work; compliance with its own safety procedures and policies; and compliance with all applicable health and safety laws, including the regulations and standards of the Occupational Safety and Health Act of 1970 ("OSHA") as amended. Contractor shall submit to the Owner the following within five (5) working days of the occurrence of an event which causes death, personal injury or property damage:
 - Completed Owner's Incident Report
 - A copy of Employer's First Report of Injury
 - A copy of other Property/Casualty insurance claim reports
 - A copy of OSHA Inspection/Citation Reports
- Interim Life Safety Measures (ILSM) will be established by Owner and Contractor for all construction projects. Any work on fire suppression and fire alarm systems must be coordinated with the Owner prior to commencing. Life Safety Plans for the buildings are available from the Owner. Penetrations of rated walls must be patched immediately. Exits must remain unobstructed and usable. If appropriate, alternate public access routes should be provided.
- Infection Control Risk Assessments (ICRA) will be completed in collaboration with the Owner prior to all construction. Required control measures will be applied as identified.
- The Owner has Asbestos Evaluation and Abatement Services which address any identified asbestos exposure. Contact the Owner Representative if asbestos is suspected.
- Construction areas are to remain fire-safe. All welding must be supervised, and a fire extinguisher must be present. Welding and cutting will be stopped one hour before the day's end. Owner's "Hot Work" permits with follow-up are required and are available through the Owner's Facilities office.
- Safety Data Sheets (SDS) on any product used in construction must be obtained by Contractor from the manufacturer and kept on file at the project site. SDS about chemicals used within the Owner's environment are available from Owner's Representative upon request. Materials which are extremely hazardous or produce strong odors must be reviewed and approved by the Owner prior to use.

Dust/Infection Control

Infection Control Guidelines are available from the Owner. Contractor personnel will comply with these guidelines. The clean environment of hospital and clinical locations must be maintained. Any construction activity must be contained within tightly sealed temporary barriers with HEPA filter exhaust fans. Trash carts must be covered when moved throughout the facilities.

Medical Gases / Utility / Equipment / Traffic Pattern Outages and Modifications

Any shutdown or modifications of medical gases, utility services, equipment, or car/pedestrian traffic patterns must be coordinated with and approved by the Owner to allow appropriate notification and scheduling with affected areas. Due diligence is mandatory regarding locating utility services prior to any soil, concrete, or other concealed disturbance. OSHA's lockout/tagout requirements must be adhered to in coordination with the Owner's practice.

Security

Contractor personnel shall abide by all Owner provided security related direction. Specifically:

- Identification/access badges shall be issued by the Owner as required and worn/used as directed.
- Owner's patient and visitor identities, along with any acquired associated information, will not be shared or discussed.
- Owner's non-public business information will remain confidential.
- Owner and Contractor shall share an integrity position that prohibits personal/company wrongful gain from a Mayo transaction.
- Closed door integrity shall be adhered to, and the use of secured doors by Contractor will be coordinated with the Owner.
- Limited access to keys will be through the Owner's key management system which contains penalties for abuse or lost keys.
- Work sites will be secured when work activity ceases.
- The use of cameras and digital recording devices is prohibited in all patient care areas.

Parking

Contractors will park off-campus except for temporary loading/unloading of materials or equipment. When parking on-campus for temporary loading or unloading the location and timing must be coordinated with owner.